


Whitegate Independent Power Plant



Engineers Ireland Site Visit
23rd March 2010

Agenda

- Presentation of project and progress to date.
- Site Tour
- Close Out



Fort Carlisle

Main Shipping Channel

Fort Mitchell (Spike Island)

Fort Davis

Naval Base & Irish Steel Site

SITE

REFINERY

WIPP Site

Refinery

Whitegate Village

Refinery Jetty

ESB Aghada Site

WHITEGATE VILLAGE

WIPP Project Summary

- **Bord Gáis are constructing a 450 MW Combined Cycle Power Plant (CCGT), located in Whitegate, Co. Cork.**
 - At 450 MW, this is the equivalent of powering approximately 135,000 homes.
- **Bord Gáis leased 25 acres of land from the adjacent ConocoPhillips oil refinery.**
- **The power plant and refinery agreed a suite of interfaces covering the supply of distillate, steam, natural gas and refinery off gas.**
- **The project is managed within the Investments Group of Bord Gáis.**
- **The power plant is being constructed under an Engineer, Procure & Construct (EPC) contract.**
- **General Electric and Gama (GE-Gama) were appointed as the EPC contractor.**
- **Bord Gáis appointed PB Power as the Owners Engineer.**
- **The EPC contract commenced in August 2007 and the Commercial Operation Date (COD) is July 2010. The Project is currently on schedule for COD July 2010.**

Project Development


- **2005**
 - Bord Gáis and ConocoPhillips agreed to explore the potential for development of a power generation plant on 25 acres of land owned by the ConocoPhillips oil refinery in Whitegate, Co. Cork.
- **2006:**
 - Heads of Terms agreed for the long-term lease of 25 acres of land from ConocoPhillips
 - Bord Gáis appointed consultants
 - Arup's for planning and environmental
 - Mott McDonald for engineering and design
 - Submitted application to EirGrid for connection to the grid.
 - Mott's developed original layout and design of plant.
 - Arup's developed planning application and EIS.
 - Planning permission for the project received in October 2006.
 - Developed Minimal Functional Specification (MFS) for EPC Tender
 - OJEC Notices:
 - Owners Engineer
 - Engineering, Procurement and Construction (EPC) for 450 MW CCGT Plant

Project Development

- **2007**

- Appoint Owners Engineer: PB Power
- GE-Gama and Siemens tender for the EPC Contract
 - Tender evaluation process
 - Preferred bidder selection
- GE-Gama selected as preferred bidder March 2007
 - Main contract based on Fidic Silver
 - Plant technical deliverables agreed within the MFS
- EPC Contract signed with GE-Gama in August 2007
- September 2007, GE-Gama mobilise to site
- October 2007, site clearance works commence
- November 2007, commence construction of site offices
- December 2007, commence diversion of Glanagow Stream

Landscape Plan & Site Layout



Key Project Milestones

• EPC Contract Award	Aug	2007
• Site Mobilisation	Oct	2007
• Civil Works	Mar	2008
• Structural Steel Erection	Sep	2008
• Mechanical Works Start	Nov	2008
• Electrical Works Start	Jan	2009
• Main Equipment Delivery	Jan	2009
• Main Equipment Installation	Feb	2009
• Electrical Back Feed	Sep	2009
• First Fire Gas Turbine	Feb	2010
<hr/>		
• Base Load Operation	Apr	2010
• Grid Code Testing	May	2010
• Performance & Reliability Run	May	2010
• AIS Commissioning (3rd Circuit)	May	2010
• Commercial Operation Date	Jul	2010
<hr/>		
• GIS Commissioning (4th Circuit)	Aug	2011

BGE External Deliverables

• Water Supply <ul style="list-style-type: none">• Cork County Council	Feb	2009
• Effluent Discharge Line <ul style="list-style-type: none">– DAFF (Foreshore Licence)	Mar	2009
• Gas Supply <ul style="list-style-type: none">– Bord Gáis Networks	Apr	2009
• IPPC Licence <ul style="list-style-type: none">– EPA	Apr	2009
• Electrical Back-feed <ul style="list-style-type: none">– EirGrid	Sep	2009
• Emissions Trading Licence <ul style="list-style-type: none">– EPA	Feb	2010
• Distillate Supply <ul style="list-style-type: none">– ConocoPhillips	Mar	2010
• Telecommunications <ul style="list-style-type: none">– Eircom (Fibre Optic connection)	Apr	2010
• Grid Connection (3rd Circuit) <ul style="list-style-type: none">– EirGrid	May	2010
• Grid Connection (4th Circuit) <ul style="list-style-type: none">– EirGrid	Aug	2011


EirGrid Circuit Routes




EirGrid Deliverables

- **Back-Feed Cable**
 - Scheduled July 2009
 - Current network line capacity is ~860 MW
 - Installed base load capacity by January 2010= ~1140 MW (450 + 420 + 270)
 - WIPP + ESB CCGT + ESB Steam Plant (ESB OCGT's not included)
- **3rd Circuit**
 - Scheduled May 2010
 - 3rd circuit increases network line capacity to ~1290 MW.
 - N-1 requirements has set grid firm access at ~860 MW: to be shared by BGE and ESB.
 - Circuit operational May 2010
- **4th Circuit**
 - Scheduled August 2011
 - Submarine cable order July 2009
 - Submarine cable installation December 2010 to February 2011
 - Circuit Operational August 2011


Gas Line & EirGrid Back-Feed and 4th Circuit Routes



3rd Circuit Route



November 2007



Clearance of Lay down area


Storage of Site Material

Site Clearance and Levelling


January 2008

**Lay-Down Area
established**

**Area for Main
Construction
Offices**



April 2008




**Site Zoned
based on layout**

August 2008



**Main
Construction
Offices Finished**

September 2008



Main Turbine Building

Bund Wall for Distillate Tank

De-Min Water Tank

East Retaining Wall

Basement of Electrical Building

Administration Building Foundation


Workshop Stores Canteen

450 MW CCGT Power Plant


- GE Single Shaft Configuration (58% efficiency)
 - 9FB Gas Turbine – 280 MW
 - A15 Steam Turbine – 150 MW
 - Supplementary Firing – 30 MW
 - 450H Class Generator – 19 kV
 - SPX- Air Cooled Condensers – 20 fan units
 - CMI Vertical Tube HRSG – 3 pressure, re-heat.
- Fuel
 - Natural Gas (primary)
 - Gas turbine, Supplementary Firing, Auxiliary Boiler
 - Distillate (secondary)
 - Gas Turbine, Auxiliary Boiler, Emergency Generator
 - Refinery Off Gas (ROG)
 - Supplementary Firing

Natural Gas Fuel Cycle for CCGT

- **Natural Gas**
 - **Bord Gáis Networks AGI**
 - Supply pressure 60 bar
 - Filters and meters only; no pressure reduction
 - **Gas Reduction Station**
 - Reduced to 38 bar
 - Gas Compressors available if supplied below 38 bar
 - **Fuel Performance Skid**
 - Filtered
 - Heated to 108 degrees C
 - **Gas Turbine**
 - 35 bar inlet to gas turbine
 - 57 tons/hr at base load (432 MW)
 - **Supplementary firing**
 - Reduced to 3 bar
 - 4 burner units inside HRSG duct
 - 5 tons/hr giving approx 30 MWe
 - 50 tons steam to the Refinery



Generator	
Type	Topgas
Rating (MVA)	500
Voltage (kV)	21
Steam turbine	
Type	ALSTOM floor mounted, triple casing, triple pressure reheat
HP turbine steam temp/pressure (°C/bar)	565/135.3
IP turbine steam temp/pressure (°C/bar)	565/28
LP turbine steam temp/pressure (°C/bar)	287.4/4.74
Power output (MW)	160.9
Heat recovery steam generator	
Type	ALSTOM OCC, horizontal gas flow, triple pressure with reheat, natural circulation
HP section steam temp/pressure (°C/bar)	566.5/138.4
IP section steam temp/pressure (°C/bar)	565.6/28.6 (hot RH)
LP section steam temp/pressure (°C/bar)	289.2/5.0



Main Air filter

HP, IP, LP Steam Drums

Pressure 170 bar

HRSG Tube Stacks

Air to Gas Turbine

19 kV transformed up to 220 kV

Gas Turbine Compressor

Gas Turbine Power Turbine

Bus Ducts Power Out to Transformer



Electrical Generator

Main Stack

Exhaust Temp 640 °C

Steam Turbine HP, IP, LP sections

Gas Turbine Unit



Energy Cycle

- **Gas Turbine (280 MW)**
 - 55 tons/hr natural gas at full load
 - Generates 2400 tons/hr exhaust gas @ 640 °C
- **HRSG**
 - Exhaust gas @ 640 °C inlet to HRSG
 - Exhaust gas @ 85 °C exit from HRSG at main stack (60 meters)
 - Generates approximately 360 tons/hr of steam in HRSG
 - Increase steam output to 400 tons/hr using supplementary firing
- **Steam to Turbines (150 to 180 MW)**
 - HP Turbine: 340 tons/hr steam @ 140 bar (560 °C)
 - Steam Exits @ 29 bar (333 °C) to Re-heater
 - Re-heater to IP Turbine: 340 tons/hr steam @ 26 bar (560 °C)
 - LP Turbine: 40 tons/hr steam @ 4 bar (300 °C)
 - 380 tons/hr Steam Exits to ACC @ 0.6 bar (38 °C).
- **Inlet Steam to Air Cooled Condensers (ACC)**
 - 20 Cooling Fans (18 operational at full load, with 2 spares)
 - Condensate exits ACC @ 34 °C
 - Returns to condensate system

Major Equipment Deliveries

- December 2008:
 - HRSG Modules (18 off) @ approx 130 tons each, delivered by road at night time.
- March 2009
 - Gas Turbine (300 tons) Barged
 - Generator (281 tons) Barged
 - Transformer (320 tons) Barged
 - HP Turbine (97 tons) Barged
 - IP/LP Turbine Delivered in sections

HRSG Structural Steel Frame



HRSG Module & Lifting Frame Attachment



HRSG Module being lifting into position



HRSG – 3 Modules in Position



HRSG – Row 5 Modules being positioned



HRSG Module Installation



Major Equipment Off Loading at ESB Aghada



Gas Turbine on Main Road through Village



Passing Under ESB Aghada Bridge on main road



Main Transformer transportation to site



Gas Turbine Passing Corkbeg



Gas Turbine Passing Corkbeg



Gas Turbine on Gantry Crane




Generator on Gantry Crane at Turbine Hall




Main Transformer on Positioning Tracks



May 2005 - Centreline



GE Facility, Albany, New York



IP/LP Steam Turbine in Lathe receiving final blade tip finish

LP Steam Section Stages 1 to 6

IP Steam Section Stages 1 to 11

Gas Turbine on Centreline



Centreline with IP/LP Rotor In Place



HP Steam Turbine on Centreline




IP/LP Steam Turbine Top Cover in Place



Lagging of HP/IP/LP Steam Turbines



Model of Air Cooled Condenser (ACC)




Example of an ACC Under Construction



Construction Area for Air Cooled Condenser (ACC)



ACC Frame Construction



ACC Fan Installation



ACC Condenser Units Streets 3 & 4



ACC A Frames for Streets 1 & 2



ACC Streets 1 to 4 Condensing Units Complete



ACC Construction Continued



ACC Side Cladding Installation



ACC Construction Complete



Current Status

- Operational to 70 MW
- Steam Blowing Process nearing completion
- Next Stages:
 - Restore all steam pipe work
 - Steam to Steam Turbines
 - Tune to Base load (430MW)
 - Performance Testing
 - Grid Compliance Testing
 - Reliability Run
 - COD

Whitegate Independent Power Plant

Thank You For Your Attention